

ADDENDUM NO. 1


to the

ENGINEERING SERVICES FOR
K STREET IMPROVEMENTS
FOR THE CITY OF CASPER PUBLIC SERVICES DEPARTMENT
CITY ENGINEERING DIVISION
by

CITY OF CASPER
200 N. David
Casper, Wyoming 82601

ADDENDUM DATE: December 03, 2015

APPROVED: (CITY OF CASPER)


Alex Sveda, P.E.
Associate Engineer

ACKNOWLEDGMENT OF RECEIPT OF
ADDENDUM (CONSULTANT)

Firm

By: Signature

Title

Date Received

ADDENDUM NO. 1

to the

ENGINEERING SERVICES FOR
K STREET IMPROVEMENTS
FOR THE CITY OF CASPER PUBLIC SERVICES DEPARTMENT
CITY ENGINEERING DIVISION
by

CITY OF CASPER
200 N. David
Casper, Wyoming 82601

ADDENDUM DATE: December 03, 2015

This addendum to the Request for Proposals is hereby made a part of the RFP for the above titled project, to the same extent as though it were originally contained therein.

All consultants are expected to thoroughly examine each item enumerated herein, regardless of its apparent application.

1. Page 1, first sentence after date - Remove and Replace with the following:

“Proposals are being requested from qualified engineering consultants to furnish design and construction administration services for the K Street Improvements Project.”

2. Page 1, PROJECT DESCRIPTION; Remove and Replace with the following:

The project consists of the following work on K Street from North Center Street to North Grant Street:

- Replacement and installation of sidewalk/curbwalk and ada ramps for improved drainage and walkability.
- Replacing old cast iron pipe water mains, to include the replacement of valves and fire hydrants; cast iron pipe would be replaced with ductile iron pipe. This includes replacement of existing 6-inch cast iron with 8-inch ductile iron from North Durbin Street to North Beech Street.
- Replace sanitary sewer mains as well as manholes. In particular, vitrified clay pipe (VCP) sewer mains would be upgraded to PVC. This includes replacement of the 15-inch VCP and associated manholes from the alley between North Durbin Street and North Beech Street to the alley between North Kimball Street and North Park Street.

- Replacement and installation of Storm Sewer lead piping, catch basins and manholes. Storm Sewer and hydrology in this area will have to be evaluated. Storm Sewer main piping in the project area is in operable condition and no replacement is anticipated.
- Replacement of curb and gutter, street asphalt surfacing and striping/crosswalks.

END OF ADDENDUM NO. 1